



**TANK REPAIR CONCEPT:
INTERNAL BLADDER TYPE LINER**



ELEVATION

SCALE: 1:250

GRAPHIC SCALES



ENTERPRISE
ENGINEERING, INC

YARMOUTH, ME

ANCHORAGE, AK

TANK 19, REDHILL


FISC PEARL, HAWAII

CONCEPT 2: BLADDER SYSTEM

PROJ. NO. 98-2325	DWG. NO.	REV. 0
DRN. GQV	CHD SJD	DATE 5/21/98
		SHT. SK-4


DATE PLOTTED: 9 MAY 98

CAD FILE NO: 2325sk4



PLAN
SCALE: 1:250

GRAPHIC SCALES



ENTERPRISE
ENGINEERING, INC

YARMOUTH, ME

ANCHORAGE, AK

TANK 19, REDHILL


FISC PEARL, HAWAII

**CONCEPT 2:
BLADDER SYSTEM**

PROJ. NO. 98-2325	DWG. NO.	REV. 0
DRN. GQV	CHD. SJD	DATE 5/21/98
		SHT. SK-5

DATE PLOTTED: 9 MAY 98

CAD FILE NO: 2325sk5



1
SK-4 SK-6
SCALE: 1:5

ENTERPRISE
ENGINEERING, INC

YARMOUTH, ME

ANCHORAGE, AK

TANK 19, REDHILL

FISC PEARL, HAWAII

CONCEPT 2: BLADDER SYSTEM DETAIL

PROJ. NO.
98-2325

DWG. NO.

REV.
0

DRN.

CHD.

SJD

DATE

5/21/98

SHT.

SK-6

DATE PLOTTED: 9 MAY 98

CAD FILE NO: 2325sk6

**INTERNAL BLADDER TYPE LINER
COST ESTIMATE - BASE BID**

SYSTEM REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: RHT19-bl

PROJECT: Red Hill Tank 19 - Bladder System
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 LS
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON 1 LS	SYSTEM UNITS/ U/M	COST/WBS UNIT	TOTAL MARKED UP COSTS			
					MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)					2,339,000			
*****PROJECT SUBTOTALS*****					542,641	1,368,311	427,705	2,338,657
	<u>DISTRIBUTED COSTS</u> <i>This level is distributed</i>	208620.00/LS	1 LS		7,800	174,980	25,840	208,620
0001	<u>-FIELD OVERHEAD</u> <i>This level is distributed</i>	208620.00/LS	1 LS		7,800	174,980	25,840	208,620
	<u>BASE BID</u>	2338656.81/LS	1 LS		542,641	1,368,311	427,705	2,338,657
10	<u>-Set-up, Prep and Demolition</u>	629458.31/LS	1 LS		133,091	391,853	104,514	629,458
1010	MAINTENANCE	563432.31/LS	1 LS		133,089	325,831	104,513	563,432
1011	REPAIR	66025.99/LS	1 LS		2	66,023	2	66,026
11	<u>-Basic Tank Repairs & Appurtanen</u>	536017.60/LS	1 LS		105,927	425,012	5,079	536,018
1110	MAINTENANCE	278179.26/LS	1 LS		13,875	264,305	0	278,179
1111	REPAIR	217490.78/LS	1 LS		82,251	130,161	5,079	217,491
1112	MINOR CONSTRUCTION	40347.55/LS	1 LS		9,801	30,546	0	40,348
12	<u>-Bladder System - Barrel</u>	402870.92/LS	1 LS		123,641	66,786	212,444	402,871
1211	REPAIR	402870.92/LS	1 LS		123,641	66,786	212,444	402,871
13	<u>-Bladder System - Lower Dome</u>	115652.82/LS	1 LS		33,293	29,249	53,111	115,653
1311	REPAIR	115652.82/LS	1 LS		33,293	29,249	53,111	115,653
14	<u>-Tell-tale System</u>	305951.16/LS	1 LS		47,656	248,105	10,191	305,951
1411	REPAIR	305951.16/LS	1 LS		47,656	248,105	10,191	305,951
15	<u>-Upper Dome Repairs</u>	107163.13/LS	1 LS		9,898	72,294	24,971	107,163
1510	MAINTENANCE	107163.13/LS	1 LS		9,898	72,294	24,971	107,163
16	<u>-Existing Tank Inspection</u>	16203.03/LS	1 LS		0	16,203	0	16,203
1610	MAINTENANCE	16203.03/LS	1 LS		0	16,203	0	16,203
17	<u>-Tank Piping - Lining</u>	225339.82/LS	1 LS		89,135	118,809	17,396	225,340
1710	MAINTENANCE	225339.82/LS	1 LS		89,135	118,809	17,396	225,340

SUMMARY REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: RHT19-bl

PROJECT: Red Hill Tank 19 - Bladder System
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 LS
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON 1 LS	SYSTEM UNITS/ U/M	COST/WBS UNIT	TOTAL MARKED UP COSTS			
					MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)					2,339,000			
*****PROJECT SUBTOTALS****					542,641	1,368,311	427,705	2,338,657
	<u>DISTRIBUTED COSTS</u>	<u>208620.00/LS</u>	<u>1 LS</u>	<u>7,800</u>	<u>174,980</u>	<u>25,840</u>	<u>208,620</u>	
	<i>This level is distributed</i>							
0001	---FIELD OVERHEAD	208620.00/LS	1 LS	7,800	174,980	25,840	208,620	
	<i>This level is distributed</i>							
	<u>BASE BID</u>	<u>2338656.81/LS</u>	<u>1 LS</u>	<u>542,641</u>	<u>1,368,311</u>	<u>427,705</u>	<u>2,338,657</u>	
10	---Set-up, Prep and Demolition	629458.31/LS	1 LS	133,091	391,853	104,514	629,458	
11	---Basic Tank Repairs & Appurt	536017.60/LS	1 LS	105,927	425,012	5,079	536,018	
12	---Bladder System - Barrel	402870.92/LS	1 LS	123,641	66,786	212,444	402,871	
13	---Bladder System - Lower Dome	115652.82/LS	1 LS	33,293	29,249	53,111	115,653	
14	---Tell-tale System	305951.16/LS	1 LS	47,656	248,105	10,191	305,951	
15	---Upper Dome Repairs	107163.13/LS	1 LS	9,898	72,294	24,971	107,163	
16	---Existing Tank Inspection	16203.03/LS	1 LS	0	16,203	0	16,203	
17	---Tank Piping - Lining	225339.82/LS	1 LS	89,135	118,809	17,396	225,340	

CONTRACTOR MARKUP REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.1
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED :EEI
 PRINTING DATE :05/27/98
 PAGE NUMBER :1
 ESTIMATE NAME : RHT19-bladde

PROJECT: Red Hill Tank 19 - Bladder System
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR:EEI
 PROJECT SIZE: 1.00LS
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE:N/A
 UIC:
 PROJECT #:
 DATE OF ESTIMATE:5/26/98
 BID DATE: 4/99

CONTRACTOR	DESCRIPTION	MATERIAL	LABOR	EQUIPMENT
P	Prime Contractor			
	WORKER'S COMPENSATION/UNEMPL/SOC. SEC TAXES	0.00	45.00	0.00
	HAWAII ADJMENT FACTOR	0.00	31.00	0.00
	PRIME OVERHEAD	10.00	10.00	10.00
	PRIME PROFIT	6.00	6.00	6.00
	PRIME HOME OFFICE	3.00	3.00	3.00
	BOND	2.00	2.00	2.00
	ESCALATION	1.02	1.02	1.02
	ESTIMATING CONTINGENCY	5.00	5.00	5.00
	HI GET	4.17	4.17	4.17
	SALES TAX	0.50	0.00	0.50
	COMPOSITE MARKUPS FOR P			
	MATERIAL COMPOSITE MARKUP	1.360		
	LABOR COMPOSITE MARKUP	2.571		
	EQUIPMENT COMPOSITE MARKUP	1.360		
S	Subcontractors			
	SUBCONTRACTOR OVERHEAD	10.00	10.00	10.00
	SUBCONTRACTOR PROFIT	6.00	6.00	6.00
	SUBCONTRACTOR HOME OFFICE	3.00	3.00	3.00
	COMPOSITE MARKUPS FOR S			
	MATERIAL COMPOSITE MARKUP	1.201		
	LABOR COMPOSITE MARKUP	1.201		
	EQUIPMENT COMPOSITE MARKUP	1.201		

PROJECT: Red Hill Tank 19 - Bladder System
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 LS
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

DETAIL REPORT
 UNBURDENED LINE ITEMS
 FACD
 SOFTWARE VERSION: SUCCESS 3.0
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT PRL 98-9

DATABASE USED: EEI
 PRINTING DATE: 05/27/1998

PROJECT: Red Hill Tank 19 - Bladder System
 CONSTRUCTION CONTRACT: PRL 98-9

PRINTING DATE: 05/27/1998
 Page No. 1

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
00							
0001							
	<u>0001 FIELD OVERHEAD</u>						
	<i>This system is distributed</i>						
010000002	Project Superintendent	7.00	mos	0	5940 41,580	0	5940 41,580
010000002	Project Quality Control	7.00	mos	0	5000 35,000	0	5000 35,000
010000002	Safety	5.00	mos	0	4800 24,000	0	4800 24,000
010000002	Equipment Operator (crane, fork truck)	5.00	mos	0	4800 24,000	0	4800 24,000
010000002	Boom Operator	5.00	mos	0	5300 26,500	0	5300 26,500
010000001	Pick-Up Truck #1	5.00	mos	0	0	720 3,600	720 3,600
010000001	Pick-Up Truck #2	5.00	mos	0	0	720 3,600	720 3,600
010000001	Skid Steer/fork lift #1	5.00	mos	0	0	2530 12,650	2530 12,650
010000001	Welding Equipment #1	5.00	mos	0	0	600 3,000	600 3,000
010000003	Contractor Office	5.00	mos	0	0	181 905	181 905
010000003	Tool & Storage Shed	5.00	mos	0	0	90 450	90 450
010000003	Temporary Toilets	5.00	mos	0	0	80 400	80 400
010000003	Small Tools	5.00	mos	750 3,750	0	0	750 3,750
010000003	Construction Schedule	1.00	ls	0	1200 1,200	0	1200 1,200
010000003	Progress Sched	5.00	mos	0	240 1,200	0	240 1,200
010000004	Photographs	5.00	mos	50 250	0	0	50 250
010000004	Submittals	2.00	wk	0	1500 3,000	0	1500 3,000

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
0001 FIELD OVERHEAD							
<i>This system is distributed</i>							
010000004	As-Built Drawings	2.00	wk	400 800	1500 3,000	0	1900 3,800
010000006	Communications: Telephone,Radios	5.00	mos	0	0	247 1,235	247 1,235
010000014	General Clean-up	5.00	mos	0	300 1,500	0	300 1,500
010000014	Mobilization	1.00	LS	3000 3,000	7000 7,000	0	10000 10,000
010000014	Demobilization	1.00	LS	0	7000 7,000	0	7000 7,000
TOTAL 0001 FIELD OVERHEAD				7,800	174,980	25,840	208,620
	1.00 LS						

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
10							
1010							
101010							
101010001 General							
	Subcontractor: S	1.00	ls	6000	9600	4500	20100
	Temp. monorail in tank (S12x35 monorail + 2 hoists)			6,000	9,600	4,500	20,100
	Subcontractor: S	10.00	mos			1025	1025
	Temp. swing staging inside tank (rented air powered, to 300' high, 2 staging)			0	0	10,250	10,250
	Subcontractor: S	2.00	ea		500		500
	Certify Booms			0	1,000	0	1,000
	Subcontractor: S	2.00	ea		500		500
	Certify Swing Staging			0	1,000	0	1,000
	Subcontractor: S	1.00	ls	13800	7393		21193
	Temp power to Const Trailers			13,800	7,393	0	21,193
	Subcontractor: S	1.00	ls	10357	6071		16428
	Elec - Upper Tunnel - Weld. elec, lights, small tools			10,357	6,071	0	16,428
	Subcontractor: S	1.00	ls	14964	4321		19285
	Elec - Lower Tunnel - Weld, elec, lights, small tools			14,964	4,321	0	19,285
02220		2.00	md		240	50	290
	Remove Exist. Aboveground Air Supply Fan at top of tank			0	480	100	580
02220		2.00	md		240	50	290
	Remove ductwork, Lower Tunnel			0	480	100	580
		40.00	md		240		240
	Remove Hoist Sys. / swing staging (4per. @ 30/hr x 8hr/day x 10 day)			0	9,600	0	9,600
		8.00	md		240		240
	Remove Lighting in Tank (2per. @ 30/hr x 8hr/day x 4 day)			0	1,920	0	1,920
		20.00	md		240		240
	Water Wash Shell & Tower (4per. @ 30/hr x 8hr/day x 5 day)			0	4,800	0	4,800
1	Subcontractor: S	5.00	day		750		750
	Marine Chemist - Evaluation			0	3,750	0	3,750
1	Subcontractor: S	3.00	day		750		750
	Marine Chemist - Safety Pan			0	2,250	0	2,250
Subtotal Direct Costs				45,121	52,665	14,950	112,736
Subcontractor Markups				9,068	7,112	2,964	19,145
Distributions				1,081	29,281	1,595	31,958
Prime Contractor P Markups				19,915	139,917	6,898	166,730
TOTAL 101010001 General				75,185	228,975	26,408	330,568
1.00 LS							

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
101010							
101010001 General							
SUBTOTAL 101010 General				45,121	52,665	14,950	112,736
MARKUP				1,666	4,348	1,766	2,932
TOTAL 101010 General				75,185	228,975	26,408	330,568
101011							
101011001 Ventilation System							
15720	Subcontractor: S Supply fan with filters, 19000 l/s, 100 hp motor (75 kw motor)	1.00	ea	14000 14,000	1000 1,000	0	15000 15,000
15720	Subcontractor: S Exhaust fan with filters, 19000 l/s, 100 hp motor (75 kw motor)	1.00	ea	16000 16,000	1500 1,500	0	17500 17,500
15810	Subcontractor: S Ductwork, 800 mm dia	50.00	m	43 2,150	62 3,100	0	105 5,250
15810	Subcontractor: S Flex duct, 300 mm dia	200.00	m	13 2,600	16 3,200	0	29 5,800
	Subcontractor: S Elec - Gen for Supply Fan	1.00	ea	0	1004 1,004	44118 44,118	45122 45,122
	Subcontractor: S Elec - Gen Demob	1.00	ea	0	11250 11,250	0	11250 11,250
Subtotal Direct Costs				34,750	21,054	44,118	99,922
Subcontractor Markups				6,984	4,231	8,867	20,082
Distributions				832	12,386	4,719	17,937
Prime Contractor P Markups				15,338	59,185	20,401	94,923
TOTAL 101011001 Ventilation System				57,904	96,856	78,105	232,865
1.00 LS							
SUBTOTAL 101011 Ventilation				34,750	21,054	44,118	99,922
MARKUP				1,666	4,600	1,770	2,330
TOTAL 101011 Ventilation				57,904	96,856	78,105	232,865
SUBTOTAL 1010 MAINTENANCE				79,871	73,719	59,068	212,658
MARKUP				1,666	4,420	1,769	2,649
TOTAL 1010 MAINTENANCE				133,089	325,831	104,513	563,432
1011							
101110							
101110001 Demo Piping & Tell-tale In Tank							
6000000	Remove Tell-tale piping, DN 20	357.00	m	0	8 2,856	0	8 2,856
6000000	Remove Tell-tale piping, DN 40	915.00	m	0	10 9,150	0	10 9,150
6000000	Remove Tell-tale jumper pipes, DN20	163.00	ea	0	10 1,630	0	10 1,630
6000000	Remove gooseneck DN 800. Fill/Issue	16.00	mh	0	25 400	0	25 400
6000000	Remove tee, reducer & valve, DN 400	12.00	mh	0	25 300	0	25 300

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
101110							
101110001 Demo Piping & Tell-tale In Tank							
6000000	Remove water piping in tank	8.00	mh	0	25	0	25
				0	200	0	200
6000000	Remove water piping in tunnel	12.00	mh	0.1	25	0.1	25.2
				1	300	1	302
6000000	Material Disposal	8000.00	kg	0	0.3	0	0.3
				0	2,400	0	2,400
Subtotal Direct Costs				1	17,236	1	17,238
Distributions				0	8,443	0	8,443
Prime Contractor P Markups				0	40,344	0	40,344
TOTAL 101110001 Demo Piping & Tell-tale In Tank				2	66,023	2	66,026
1.00 LS							
SUBTOTAL 101110 Demo Piping & Tell-tale In Tank				1	17,236	1	17,238
MARKUP				1.383	3,831	1.475	3,830
TOTAL 101110 Demo Piping & Tell-tale In Tank				2	66,023	2	66,026
SUBTOTAL 1011 REPAIR				1	17,236	1	17,238
MARKUP				1.383	3,831	1.475	3,830
TOTAL 1011 REPAIR				2	66,023	2	66,026

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
11							
1110							
111010							
	<u>111010001 Basic Tank Repairs & Appurtanences</u>						
	Remove Grout Tubes	500.00	ea	0	16 8,000	0	16 8,000
	Remove All Misc Clips / Debris	1.00	ea	0	1000 1,000	0	1000 1,000
	Patch Plate Holes at Removed Tell tale Piping / Grout Tubes	1000.00	ea	10 10,000	60 60,000	0	70 70,000
	Subtotal Direct Costs			10,000	69,000	0	79,000
	Distributions			199	33,799	0	33,999
	Prime Contractor P Markups			3,675	161,505	0	165,180
	TOTAL 111010001 Basic Tank Repairs & Appurtanences			13,875	264,305	0	278,179
	1.00 LF						
	SUBTOTAL 111010 Basic Tank Repairs & Appurtanences			10,000	69,000	0	79,000
	MARKUP			1.387	3.831		3.521
	TOTAL 111010 Basic Tank Repairs & Appurtanences			13,875	264,305	0	278,179
	SUBTOTAL 1110 MAINTENANCE			10,000	69,000	0	79,000
	MARKUP			1.387	3.831		3.521
	TOTAL 1110 MAINTENANCE			13,875	264,305	0	278,179
1111							
111110							
	<u>111110001 Basic Tank Repairs & Appurtanences</u>						
	Subcontractor: S	4.00	m	2300	1050	440	3790
	Tank Piping - DN 800 diffuser			9,200	4,200	1,760	15,160
	Subcontractor: S	2.00	m	583	262	110	955
	Tank Piping - DN 400 piping mods.			1,166	524	220	1,910
	Subcontractor: S	2.00	m	146	66	28	240
	Tank Piping - DN 200 piping mods			292	132	56	480
	Subcontractor: S	1.00	ls	2000	2400		4400
	Tank Piping - Hydrotest			2,000	2,400	0	4,400
	Tank straping & calibration	1.00	ls	0	12000	1000	13000
					12,000	1,000	13,000
	Tower Mods. - Reinf @ Dome for Boom Operation, 4 per @ 30/hr x 8hr/day x 7 days)*	7.00	md	1000 7,000	240 1,680	0	1240 8,680
	Tower Mods. - Provide Gauging Platform	10.00	md	1000 10,000	240 2,400	0	1240 12,400
	Tank ATG - Remove existing gauge system	2.00	md	0	240 480	0	240 480
	ATG system (type to be determined)	1.00	ea	25000 25,000	1500 1,500	0	26500 26,500

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
111110							
111110001 Basic Tank Repairs & Appurtanences							
	Subcontractor: S	1.00	ea		1000		1000
Tank ATG - System testing				0	1,000	0	1,000
	Subcontractor: S	1.00	ea	1732	5000		6732
Elec wire and conduits for ATG system				1,732	5,000	0	6,732
Subtotal Direct Costs				56,390	31,316	3,036	90,742
Subcontractor Markups				2,892	2,664	409	5,965
Distributions				1,182	16,645	307	18,134
Prime Contractor P Markups				21,787	79,536	1,327	102,649
TOTAL 111110001 Basic Tank Repairs & Appurtanences				82,251	130,161	5,079	217,491
1.00 LF							
SUBTOTAL 111110 Basic Tank Repairs & Appurtanences				56,390	31,316	3,036	90,742
MARKUP				1,459	4,156	1,673	2,397
TOTAL 111110 Basic Tank Repairs & Appurtanences				82,251	130,161	5,079	217,491
SUBTOTAL 1111 REPAIR				56,390	31,316	3,036	90,742
MARKUP				1,459	4,156	1,673	2,397
TOTAL 1111 REPAIR				82,251	130,161	5,079	217,491
1112							
111210							
111210001 Basic Tank Repairs & Appurtanences							
1	Subcontractor: S	1.00	ea	3500	1000		4500
Hi level control panel, Scully system				3,500	1,000	0	4,500
1	Subcontractor: S	2.00	ea	250	80		330
Hi level alarm sensors				500	160	0	660
1	Subcontractor: S	1.00	ea	150	480		630
Hi level alarm sensor holder, tank mods				150	480	0	630
	Subcontractor: S	1.00	ea	1732	5000		6732
Elec wire and conduits for hi level alarm system				1,732	5,000	0	6,732
Subtotal Direct Costs				5,882	6,640	0	12,522
Subcontractor Markups				1,182	1,335	0	2,517
Distributions				141	3,906	0	4,047
Prime Contractor P Markups				2,596	18,666	0	21,262
TOTAL 111210001 Basic Tank Repairs & Appurtanences				9,801	30,546	0	40,348
1.00 LF							
SUBTOTAL 111210 Basic Tank Repairs & Appurtanences				5,882	6,640	0	12,522
MARKUP				1,666	4,600		3,222
TOTAL 111210 Basic Tank Repairs & Appurtanences				9,801	30,546	0	40,348
SUBTOTAL 1112 MINOR CONSTRUCTION				5,882	6,640	0	12,522
MARKUP				1,666	4,600		3,222
TOTAL 1112 MINOR CONSTRUCTION				9,801	30,546	0	40,348

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
111210							
	<u>111210001 Basic Tank Repairs & Appurtanences</u>						

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
12							
1211							
121110							
121110001 Bladder System - Barrel							
1	Prep 100% barrel surface (grind sharp edges, remove protrusions)	15.00	md	0	240 3,600	0	240 3,600
	Subcontractor: S	4400.00	m2	0.1 440	0	0	0.1 440
	Bladder cushion (12 oz/sy)	3.00	md	0	240 720	0	240 720
	Subcontractor: S	12.00	md	0.1 1	240 2,880	0	240.1 2,881
	Transport cushion to tunnel	4400.00	m2	12.9 56,760	0	0	12.9 56,760
	Subcontractor: S	12.00	md	0	240 2,880	0	240 2,880
	Transport bladder thru tunnel	1.00	ls	0	0	120000 120,000	120000 120,000
	Subcontractor: S	2.00	ea	7000 14,000	0	0	7000 14,000
	Batten plate (top and bottom) (quote)	14.00	md	0	240 3,360	0	240 3,360
	Subcontractor: S	7.00	md	0	240 1,680	0	240 1,680
	Test field seams	1.00	ls	3000 3,000	0	0	3000 3,000
	Subcontractor: S						
	QA/QC (liner rep. on-site)						
	Material Freight (Quote)						
	Subtotal Direct Costs			74,201	15,120	120,000	209,321
	Subcontractor Markups			14,913	2,315	24,118	41,346
	Distributions			1,777	8,541	12,835	23,153
	Prime Contractor P Markups			32,750	40,810	55,491	129,051
	TOTAL 121110001 Bladder System - Barrel			123,641	66,786	212,444	402,871
	1.00 LF						
	SUBTOTAL 121110 Bladder System - Barrel			74,201	15,120	120,000	209,321
	MARKUP			1.666	4.417	1.770	1.925
	TOTAL 121110 Bladder System - Barrel			123,641	66,786	212,444	402,871
	SUBTOTAL 1211 REPAIR			74,201	15,120	120,000	209,321
	MARKUP			1.666	4.417	1.770	1.925
	TOTAL 1211 REPAIR			123,641	66,786	212,444	402,871

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
13							
1312							
131210							
131210001	Bladder System - Lower Dome						
1	Prep 100% barrel surface (grind sharp edges, remove protrusions)	10.00	md	0	240 2,400	0	240 2,400
	Subcontractor: S	1460.00	m2	0.1 146	0	0	0.1 146
	Bladder cushion (12 oz/sy)						
	Subcontractor: S	1.50	md	0	240 360	0	240 360
	Transport cushion thru tunnel						
	Subcontractor: S	4.00	md	0	240 960	0	240 960
	Attach cushion to dome						
	Subcontractor: S	1460.00	m2	12.9 18,834	0	0	12.9 18,834
	30 mil bladder						
	Transport bladder thru tunnel	2.00	md	0	240 480	0	240 480
	Subcontractor: S	1.00	ls	0	0	30000 30,000	30000 30,000
	Install bladder in tank (quote)						
	Subcontractor: S	8.00	md	0	240 1,920	0	240 1,920
	Test field seams						
	Subcontractor: S	3.00	md	0	240 720	0	240 720
	QA/QC (liner rep. on-site)						
	Subcontractor: S	1.00	ls	1000 1,000	0	0	1000 1,000
	Material Freight (Quote)						
	Subtotal Direct Costs			19,980	6,840	30,000	56,820
	Subcontractor Markups			4,016	796	6,029	10,841
	Distributions			479	3,740	3,209	7,428
	Prime Contractor P Markups			8,819	17,873	13,873	40,564
	TOTAL 131210001 Bladder System - Lower Dome			33,293	29,249	53,111	115,653
	1.00 LF						
	SUBTOTAL 131110 Bladder System - Lower Dome			19,980	6,840	30,000	56,820
	MARKUP			1.666	4.276	1.770	2.035
	TOTAL 131110 Bladder System - Lower Dome			33,293	29,249	53,111	115,653
	SUBTOTAL 1311 REPAIR			19,980	6,840	30,000	56,820
	MARKUP			1.666	4.276	1.770	2.035
	TOTAL 1311 REPAIR			33,293	29,249	53,111	115,653

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
14							
1411							
141110							
141110001	New Tell-tale System - Piping to Sump						
15192	Pipe, DN 40, Sched 80, including fittings	785.00	m	17 13,345	27 21,195	3 2,355	47 36,895
15192	Pipe, DN 50, Sched 80, including fittings	26.00	m	21 546	34 884	4 104	59 1,534
15192	Pipe, DN 150, Sched 80, including fittings	17.00	m	107 1,819	102 1,734	7 119	216 3,672
15192	Pipe, DN 450, Sched 40, including fittings	10.00	m	660 6,600	450 4,500	31 310	1,141 11,410
15192	Valve, DN 40, Gate	13.00	ea	150 1,950	55 715	6 78	211 2,743
15192	Valve, DN 50, Gate	1.00	ea	190 190	70 70	8 8	268 268
09000	Subcontractor: S NDE welds	30.00	md	0	240 7,200	0	240 7,200
09000	Subcontractor: S Hydrotest telltale	8.00	md	0	240 1,920	0	240 1,920
Subtotal Direct Costs				24,450	38,218	2,974	65,642
Subcontractor Markups				0	1,833	0	1,833
Distributions				488	19,619	265	20,371
Prime Contractor P Markups				8,986	93,746	1,145	103,876
TOTAL 141110001 New Tell-tale System - Piping to Sump				33,923	153,415	4,384	191,722
1.00 LS							
141110002	New Tell-tale System - Piping to Sump - Structural						
03000	Grout	1.00	LS	500 500	400 400	0	900 900
02220	Subcontractor: S Drill concrete, 254 mm dia.	17.00	M	125 2,125	250 4,250	40 680	415 7,055
02220	Subcontractor: S Drill concrete, 610 mm dia	10.00	M	570 5,700	1600 16,000	260 2,600	2430 24,300
Subtotal Direct Costs				8,325	20,650	3,280	32,255
Subcontractor Markups				1,573	4,070	659	6,302
Distributions				197	12,109	351	12,657
Prime Contractor P Markups				3,637	57,861	1,517	63,015
TOTAL 141110002 New Tell-tale System - Piping to Sump - Structural				13,733	94,689	5,807	114,229
1.00 LS							
SUBTOTAL 141110 New Tell-tale System				32,775	58,868	6,254	97,897
MARKUP				1,454	4,215	1,629	3,125
TOTAL 141110 New Tell-tale System				47,656	248,105	10,191	305,951

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
141110	<u>141110002 New Tell-tale System - Piping to Sump - Structural</u>						
SUBTOTAL 1411 REPAIR				32,775	58,868	6,254	97,897
MARKUP				1,454	4,215	1,629	3,125
TOTAL 1411 REPAIR				47,656	248,105	10,191	305,951

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
15							
1510							
151010							
	<u>151010001 Upper Dome Repairs</u>						
	Subcontractor: S	5.00	days			2821	2821
	UTscan 10% Dome			0	0	14,105	14,105
	Patch plate thin spots/holes	250.00	ea	10	60		70
				2,500	15,000	0	17,500
	Subcontractor: S	75.00	m2	51.45	43		94.45
	Spot coating repai (5% dome surface area)			3,859	3,225	0	7,084
	Subtotal Direct Costs			6,359	18,225	14,105	38,689
	Subcontractor Markups			776	648	2,835	4,259
	Distributions			142	9,245	1,509	10,896
	Prime Contractor P Markups			2,622	44,176	6,523	53,320
	TOTAL 151010001 Upper Dome Repairs			9,898	72,294	24,971	107,163
	1.00 LF						
	SUBTOTAL 151010 Upper Dome Repairs			6,359	18,225	14,105	38,689
	MARKUP			1.557	3.967	1.770	2.770
	TOTAL 151010 Upper Dome Repairs			9,898	72,294	24,971	107,163
	SUBTOTAL 1510 MAINTENANCE			6,359	18,225	14,105	38,689
	MARKUP			1.557	3.967	1.770	2.770
	TOTAL 1510 MAINTENANCE			9,898	72,294	24,971	107,163

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
16							
1610							
161010							
161010001	Existing Tank Inspection						
	UTscan exist. shell pl. at batten pl. (subcontractor quote)	3.00	md	0	1410 4,230	0	1410 4,230
	Subtotal Direct Costs			0	4,230	0	4,230
	Distributions			0	2,072	0	2,072
	Prime Contractor P Markups			0	9,901	0	9,901
	TOTAL 161010001 Existing Tank Inspection			0	16,203	0	16,203
	1.00 LF						
	SUBTOTAL 161010 Existing Tank Inspection			0	4,230	0	4,230
	MARKUP				3.831		3.831
	TOTAL 161010 Existing Tank Inspection			0	16,203	0	16,203
	SUBTOTAL 1610 MAINTENANCE			0	4,230	0	4,230
	MARKUP				3.831		3.831
	TOTAL 1610 MAINTENANCE			0	16,203	0	16,203

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
17							
1710							
171010							
	<u>171010001 Tank Piping - Lining</u>						
15192	Subcontractor: S	17.00	m	2300	1050	440	3790
	Tank Piping - Fuel, Pipe Lining - DN 800			39,100	17,850	7,480	64,430
15192	Subcontractor: S	17.00	m	583	262	110	955
	Tank Piping - Fuel, Pipe Lining - DN 400			9,911	4,454	1,870	16,235
15192	Subcontractor: S	17.00	m	146	66	28	240
	Tank Piping - Fuel, Pipe Lining - DN 200			2,482	1,122	476	4,080
	Subcontractor: S	1.00	ls	2000	2400		4400
	Tank Piping - Hydrotest			2,000	2,400	0	4,400
	Subtotal Direct Costs			53,493	25,826	9,826	89,145
	Subcontractor Markups			10,751	5,191	1,975	17,916
	Distributions			1,281	15,193	1,051	17,526
	Prime Contractor P Markups			23,610	72,599	4,544	100,753
	TOTAL 171010001 Tank Piping - Lining			89,135	118,809	17,396	225,340
	1.00 LF						
	 SUBTOTAL 171010 Tank Piping - Lining			53,493	25,826	9,826	89,145
	MARKUP			1.666	4.600	1.770	2.528
	TOTAL 171010 Tank Piping - Lining			89,135	118,809	17,396	225,340
	 SUBTOTAL 1710 MAINTENANCE			53,493	25,826	9,826	89,145
	MARKUP			1.666	4.600	1.770	2.528
	TOTAL 1710 MAINTENANCE			89,135	118,809	17,396	225,340

**INTERNAL BLADDER TYPE LINER
COST ESTIMATE - ADDITIVE BID ITEMS**

SYSTEM REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-Blad

PROJECT: Red Hill Tank 19 - Bladder - Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON 1 PRL 98	SYSTEM UNITS/ U/M	COST/WBS UNIT	TOTAL MARKED UP COSTS			
					MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)					747,000			
*****PROJECT SUBTOTALS*****					97,880	560,490	88,985	747,356
	<u>ADDITIVE BID ITEMS</u>	747355.80/PRL	1 LS		97,880	560,490	88,985	747,356
35	<u>-Cathodic Protection</u>	550955.13/PRL	1 LS		77,020	473,925	11	550,955
3510	MAINTENANCE	550955.13/PRL	1 LS		77,020	473,925	11	550,955
40	<u>-Under Tank Leak Detection</u>	85311.61/PRL	1 LS		0	0	85,312	85,312
4010	MINOR CONSTRUCTION	85311.61/PRL	1 LS		0	0	85,312	85,312
45	<u>-New Tell-tale System - Piping T</u>	111089.06/PRL	1 LS		20,861	86,565	3,663	111,089
4510	MAINTENANCE	111089.06/PRL	1 LS		20,861	86,565	3,663	111,089

SUMMARY REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-Blad

PROJECT: Red Hill Tank 19 - Bladder - Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON	SYSTEM	COST/WBS	TOTAL MARKED UP COSTS			
		1 PRL 98	UNITS/ U/M	UNIT	MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)								747,000
*****PROJECT SUBTOTALS*****					97,880	560,490	88,985	747,356
	<u>ADDITIVE BID ITEMS</u>	<u>747355.80/PRL</u>	<u>1 LS</u>		<u>97,880</u>	<u>560,490</u>	<u>88,985</u>	<u>747,356</u>
35	---Cathodic Protection	550955.13/PRL	1 LS		77,020	473,925	11	550,955
40	---Under Tank Leak Detection	85311.61/PRL	1 LS		0	0	85,312	85,312
45	---New Tell-tale System - Pipi	111089.06/PRL	1 LS		20,861	86,565	3,663	111,089

CONTRACTOR MARKUP REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.1
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED :EEI
 PRINTING DATE :05/27/98
 PAGE NUMBER : 1
 ESTIMATE NAME : T19-Bladder

PROJECT: Red Hill Tank 19 - Bladder - Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR:EEI
 PROJECT SIZE: 1.00PRL 98-9
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE:N/A
 UIC:
 PROJECT #:
 DATE OF ESTIMATE:5/26/98
 BID DATE: 4/99

CONTRACTOR	DESCRIPTION	MATERIAL	LABOR	EQUIPMENT
P	Prime Contractor			
	WORKER'S COMPENSATION/UNEMPL/SOC. SEC TAXES	0.00	32.00	0.00
	Hawaii cost adjustment compared to AK	0.00	31.00	0.00
	PRIME OVERHEAD	10.00	10.00	10.00
	PRIME PROFIT	6.00	6.00	6.00
	PRIME HOME OFFICE	3.00	3.00	3.00
	BOND	1.00	1.00	1.00
	ESCALATION	1.02	1.02	1.02
	ESTIMATING CONTINGENCY	5.00	5.00	5.00
	HI GET	4.17	4.17	4.17
	SALES TAX	0.50	0.00	0.50
	COMPOSITE MARKUPS FOR P			
	MATERIAL COMPOSITE MARKUP	1.347		
	LABOR COMPOSITE MARKUP	2.318		
	EQUIPMENT COMPOSITE MARKUP	1.347		
S	Subcontractors			
	SUBCONTRACTOR OVERHEAD	10.00	10.00	10.00
	SUBCONTRACTOR PROFIT	6.00	6.00	6.00
	SUBCONTRACTOR HOME OFFICE	3.00	3.00	3.00
	COMPOSITE MARKUPS FOR S			
	MATERIAL COMPOSITE MARKUP	1.201		
	LABOR COMPOSITE MARKUP	1.201		
	EQUIPMENT COMPOSITE MARKUP	1.201		

PROJECT: Red Hill Tank 19 - Bladder - Additive Bi
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

DETAIL REPORT
 UNBURDENED LINE ITEMS
 FACD
 SOFTWARE VERSION: SUCCESS 3.0
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT PRL 98-9

DATABASE USED: EEI
 PRINTING DATE: 05/27/1998

PROJECT: Red Hill Tank 19 - Bladder - Additive Bi
 CONSTRUCTION CONTRACT: PRL 98-9

PRINTING DATE: 05/27/1998
 Page No. 1

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
35							
3510							
351010							
351010001	Cathodic Protection						
	Anodes (MMO 19.1 mm x 1219 mm)	48.00	ea	150 7,200	8 384	0	158 7,584
	Anode Ventralizer Assembly	48.00	ea	28 1,344	8 384	0	36 1,728
	Anode Lead Wire, No 4 AWG, HMWPE	869.00	m	1.27 1,104	0	0	1.27 1,104
	Subcontractor: S Anode Hole Drilling & Backfilling Complete	580.00	m	0	255 147,900	0	255 147,900
	Subcontractor: S Coke Backfill	13581.00	kg	1.5 20,372	0	0	1.5 20,372
	Subcontractor: S Cement Grout	6.67	m3	140 934	0	1 7	141 940
	Anode Vent Pipe	580.00	m	3.56 2,065	0	0	3.56 2,065
	Custom Anode Junction Box (NEMA 4X)	4.00	ea	280 1,120	295 1,180	0	575 2,300
	Oil-Cooled Rectifier, 50 Volt, 200 DC Amp	1.00	ea	3100 3,100	1500 1,500	0	4600 4,600
	Rectifier Oil	322.00	liters	1.58 509	7 2,254	0	8.58 2,763
	Subcontractor: S 240 Volt, 20 Amp AC power for rectifier	1.00	ea	760 760	1100 1,100	0	1860 1,860
	Subcontractor: S AC Disconnect Switch, Fused 3P-40 Amp	1.00	ea	220 220	120 120	0	340 340
	Rectifier Pipe Bollards complete	3.00	ea	32 96	110 330	0	142 426
	Subcontractor: S Micro Directional Drill for 5 Ref Electrodes	60.00	m	0	32 1,920	0	32 1,920
	Reference Electrodes (2 per hole)	10.00	ea	245 2,450	0	0	245 2,450
	Concrete Electrical Pull Box	4.00	ea	190 760	32 128	0	222 888
	Concrete Pads (inc rebar & forms)	0.72	m3	155 112	616 444	0	771 555

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
351010							
<u>351010001 Cathodic Protection</u>							
	Cathode Header Cable, # 2/0 AWG HMP/PE	50.00	m	5.04 252	7 350	0	12.04 602
	Anode Header Cable, #2/0 AWG HMP/PE	320.00	m	5.04 1,613	2.12 678	0	7.16 2,291
	50 mm PVC conduit (anode cables)	320.00	m	5 1,600	2.12 678	0	7.12 2,278
	Subcontractor: S Trenching (Min. 0.1 m wide x 0.68 m deep)	150.00	m	0	5.5 825	0	5.5 825
	Subcontractor: S Trench Backfilling & Compaction	150.00	m	0	5.5 825	0	5.5 825
	Subcontractor: S Bedding Sand (Min. 0.1 m wide x 0.16 m deep)	2.40	m3	120 288	0	0	120 288
	Cathodic Protection construction foreman	256.00	hrs	0	20 5,120	0	20 5,120
	QC Specialist, Corrosion Engineer	256.00	hrs	26.35 6,746	30 7,680	0	56.35 14,426
Subtotal Direct Costs				52,642	173,800	7	226,449
Subcontractor Markups				4,537	30,688	1	35,226
Prime Contractor P Markups				19,840	269,437	3	289,280
TOTAL 351010001 Cathodic Protection				77,020	473,925	11	550,955
1.00 LS							
SUBTOTAL 351010 Cathodic Protection				52,642	173,800	7	226,449
MARKUP				1.463	2.727	1.610	2.433
TOTAL 351010 Cathodic Protection				77,020	473,925	11	550,955
SUBTOTAL 3510 MAINTENANCE				52,642	173,800	7	226,449
MARKUP				1.463	2.727	1.610	2.433
TOTAL 3510 MAINTENANCE				77,020	473,925	11	550,955

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
40							
4010							
401010							
	401010001 Under Tank Leak Detection						
	Subcontractor: S	10.00	day			3500	3500
	Drill Rig (10) 38 to 50 DN Directional			0	0	35,000	35,000
	Boring x 46 long ea						
	Subcontractor: S	1.00	ls			18000	18000
	Mob/Demob			0	0	18,000	18,000
	Subtotal Direct Costs			0	0	53,000	53,000
	Subcontractor Markups			0	0	10,652	10,652
	Prime Contractor P Markups			0	0	21,660	21,660
	TOTAL 401010001 Under Tank Leak Detection			0	0	85,312	85,312
	1.00 LS						
	SUBTOTAL 401010 Under Tank Leak Detection			0	0	53,000	53,000
	MARKUP					1,610	1,610
	TOTAL 401010 Under Tank Leak Detection			0	0	85,312	85,312
	SUBTOTAL 4010 MINOR CONSTRUCTION			0	0	53,000	53,000
	MARKUP					1,610	1,610
	TOTAL 4010 MINOR CONSTRUCTION			0	0	85,312	85,312

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
45							
4510							
451000							
	<u>4510001 New Tell-tale System - Piping to top of tank</u>						
		911.00	m	17	41	3	61
	Pipe, DN 40, Sched 80			15,487	37,351	2,733	55,571
	Subtotal Direct Costs			15,487	37,351	2,733	55,571
	Prime Contractor P Markups			5,374	49,214	930	55,518
	TOTAL 4510001 New Tell-tale System - Piping to top of tank			20,861	86,565	3,663	111,089
	1.00 LS						
	SUBTOTAL 451010 New Tell-tale System - Piping to top of tank			15,487	37,351	2,733	55,571
	MARKUP			1,347	2,318	1,340	1,999
	TOTAL 451010 New Tell-tale System - Piping to top of tank			20,861	86,565	3,663	111,089
	SUBTOTAL 4510 MAINTENANCE			15,487	37,351	2,733	55,571
	MARKUP			1,347	2,318	1,340	1,999
	TOTAL 4510 MAINTENANCE			20,861	86,565	3,663	111,089