



**TANK REPAIR CONCEPT:
REPAIR AND RECOAT EXISTING TANK**



GRAPHIC SCALES



ENTERPRISE
ENGINEERING, INC

YARMOUTH, ME

ANCHORAGE, AK

TANK 19, REDHILL


FISC PEARL, HAWAII

CONCEPT 3: REHABILITATE TANK

PROJ. NO. 98-2325	DWG. NO.	REV. 0
DRN. GQV	CHD. SJD	DATE 5/21/98
		SHT. SK-7


DATE PLOTTED: 9 MAY 98

CAD FILE NO: 2325sk7



PLAN
SCALE: 1:250

GRAPHIC SCALES



ENTERPRISE
ENGINEERING, INC

YARMOUTH, ME

ANCHORAGE, AK

TANK 19, REDHILL

FISC PEARL, HAWAII

**CONCEPT 3:
REHABILITATE TANK**

PROJ. NO. 98-2325	DWG. NO.	REV. 0
DRN. GQV	CHD. SJD	DATE 5/21/98
		SHT. SK-8

DATE PLOTTED: 9 MAY 98

CAD FILE NO: 2325sk8

**REPAIR AND RECOAT EXISTING TANK
COST ESTIMATE - BASE BID**

SYSTEM REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-repe

PROJECT: Red Hill Tank 19 - Repair Existing
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON 1 PRL 98	SYSTEM UNITS/ U/M	COST/WBS UNIT	TOTAL MARKED UP COSTS			
					MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)					4,610,000			
*****PROJECT SUBTOTALS****					1,237,583	2,644,768	727,922	4,610,273
	<u>DISTRIBUTED COSTS</u> <i>This level is distributed</i>	<u>423740.00/PRL</u>	<u>1 LS</u>		<u>4,700</u>	<u>343,480</u>	<u>75,560</u>	<u>423,740</u>
0001	<u>-FIELD OVERHEAD</u> <i>This level is distributed</i>	<u>423740.00/PRL</u>	<u>1 LS</u>		<u>4,700</u>	<u>343,480</u>	<u>75,560</u>	<u>423,740</u>
	<u>BASE BID</u>	<u>4610273.48/PRL</u>	<u>1 LS</u>		<u>1,237,583</u>	<u>2,644,768</u>	<u>727,922</u>	<u>4,610,273</u>
10	<u>-Set-up, Prep and Demolition</u>	<u>979994.94/PRL</u>	<u>1 LS</u>		<u>360,664</u>	<u>494,774</u>	<u>124,557</u>	<u>979,995</u>
1010	MAINTENANCE	925041.25/PRL	1 LS		360,662	439,824	124,555	925,041
1011	REPAIR	54953.71/PRL	1 LS		2	54,950	2	54,954
11	<u>-Basic Tank Repairs & Appurtanen</u>	<u>545795.15/PRL</u>	<u>1 LS</u>		<u>104,395</u>	<u>435,658</u>	<u>5,742</u>	<u>545,795</u>
1110	MAINTENANCE	278080.09/PRL	1 LS		13,674	264,406	0	278,080
1111	REPAIR	227274.46/PRL	1 LS		81,061	140,471	5,742	227,274
1112	MINOR CONSTRUCTION	40440.59/PRL	1 LS		9,659	30,781	0	40,441
12	<u>-Repair Exist.Tank - Lower Dome</u>	<u>386338.27/PRL</u>	<u>1 LS</u>		<u>54,400</u>	<u>331,939</u>	<u>0</u>	<u>386,338</u>
1210	MAINTENANCE	386338.27/PRL	1 LS		54,400	331,939	0	386,338
13	<u>-Repair Exist.Tank - Barrel</u>	<u>859323.34/PRL</u>	<u>1 LS</u>		<u>145,944</u>	<u>713,380</u>	<u>0</u>	<u>859,323</u>
1310	MAINTENANCE	859323.34/PRL	1 LS		145,944	713,380	0	859,323
14	<u>-Tell-tale System</u>	<u>232628.05/PRL</u>	<u>1 LS</u>		<u>35,692</u>	<u>188,340</u>	<u>8,596</u>	<u>232,628</u>
1411	REPAIR	232628.05/PRL	1 LS		35,692	188,340	8,596	232,628
15	<u>-Upper Dome Repairs</u>	<u>109281.82/PRL</u>	<u>1 LS</u>		<u>9,755</u>	<u>72,849</u>	<u>26,677</u>	<u>109,282</u>
1510	MAINTENANCE	109281.82/PRL	1 LS		9,755	72,849	26,677	109,282
16	<u>-Existing Tank Investigation</u>	<u>471564.60/PRL</u>	<u>1 LS</u>		<u>23,929</u>	<u>288,106</u>	<u>159,529</u>	<u>471,565</u>
1610	MAINTENANCE	471564.60/PRL	1 LS		23,929	288,106	159,529	471,565
17	<u>-Recoat Exist.Tank - Lower Dome</u>	<u>193561.59/PRL</u>	<u>1 LS</u>		<u>105,409</u>	<u>0</u>	<u>88,153</u>	<u>193,562</u>
1710	MAINTENANCE	193561.59/PRL	1 LS		105,409	0	88,153	193,562
18	<u>-Recoat Exist.Tank - Barrel</u>	<u>605633.25/PRL</u>	<u>1 LS</u>		<u>309,549</u>	<u>0</u>	<u>296,085</u>	<u>605,633</u>
1810	MAINTENANCE	605633.25/PRL	1 LS		309,549	0	296,085	605,633
19	<u>-Tank Piping - Lining</u>	<u>226152.50/PRL</u>	<u>1 LS</u>		<u>87,846</u>	<u>119,722</u>	<u>18,584</u>	<u>226,153</u>
1910	MAINTENANCE	226152.50/PRL	1 LS		87,846	119,722	18,584	226,153

SUMMARY REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-repe

PROJECT: Red Hill Tank 19 - Repair Existing
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON	SYSTEM	COST/WBS	TOTAL MARKED UP COSTS			
		1 PRL 98	UNITS/ U/M	UNIT	MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)								4,610,000
*****PROJECT SUBTOTALS*****					1,237,583	2,644,768	727,922	4,610,273
	<u>DISTRIBUTED COSTS</u>	<u>423740.00/PRL</u>	<u>1 LS</u>	<u>4,700</u>	<u>343,480</u>	<u>75,560</u>	<u>423,740</u>	
	<i>This level is distributed</i>							
0001	---FIELD OVERHEAD	423740.00/PRL	1 LS	4,700	343,480	75,560	423,740	
	<i>This level is distributed</i>							
	<u>BASE BID</u>	<u>4610273.48/PRL</u>	<u>1 LS</u>	<u>1,237,583</u>	<u>2,644,768</u>	<u>727,922</u>	<u>4,610,273</u>	
10	---Set-up, Prep and Demolition	979994.94/PRL	1 LS	360,664	494,774	124,557	979,995	
11	---Basic Tank Repairs & Appurt	545795.15/PRL	1 LS	104,395	435,658	5,742	545,795	
12	---Repair Exist.Tank - Lower D	386338.27/PRL	1 LS	54,400	331,939	0	386,338	
13	---Repair Exist.Tank - Barrel	859323.34/PRL	1 LS	145,944	713,380	0	859,323	
14	---Tell-tale System	232628.05/PRL	1 LS	35,692	188,340	8,596	232,628	
15	---Upper Dome Repairs	109281.82/PRL	1 LS	9,755	72,849	26,677	109,282	
16	---Existing Tank Investigation	471564.60/PRL	1 LS	23,929	288,106	159,529	471,565	
17	---Recoat Exist.Tank - Lower D	193561.59/PRL	1 LS	105,409	0	88,153	193,562	
18	---Recoat Exist.Tank - Barrel	605633.25/PRL	1 LS	309,549	0	296,085	605,633	
19	---Tank Piping - Lining	226152.50/PRL	1 LS	87,846	119,722	18,584	226,153	

CONTRACTOR MARKUP REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.1
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED :EEI
 PRINTING DATE :05/27/98
 PAGE NUMBER :1
 ESTIMATE NAME : T19-repexis

PROJECT: Red Hill Tank 19 - Repair Existing
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1.00PRL 98-9
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE:N/A
 UIC:
 PROJECT #:
 DATE OF ESTIMATE:5/26/98
 BID DATE: 4/99

CONTRACTOR	DESCRIPTION	MATERIAL	LABOR	EQUIPMENT
P	Prime Contractor			
	WORKER'S COMPENSATION/UNEMPL/SOC. SEC TAXES	0.00	45.00	0.00
	Hawaii cost adjustment compared to AK	0.00	31.00	0.00
	PRIME OVERHEAD	10.00	10.00	10.00
	PRIME PROFIT	6.00	6.00	6.00
	PRIME HOME OFFICE	3.00	3.00	3.00
	BOND	2.00	2.00	2.00
	ESCALATION	1.02	1.02	1.02
	ESTIMATING CONTINGENCY	5.00	5.00	5.00
	HI GET	4.17	4.17	4.17
	SALES TAX	0.50	0.00	0.50
	COMPOSITE MARKUPS FOR P			
	MATERIAL COMPOSITE MARKUP	1.360		
	LABOR COMPOSITE MARKUP	2.571		
	EQUIPMENT COMPOSITE MARKUP	1.360		
S	Subcontractors			
	SUBCONTRACTOR OVERHEAD	10.00	10.00	10.00
	SUBCONTRACTOR PROFIT	6.00	6.00	6.00
	SUBCONTRACTOR HOME OFFICE	3.00	3.00	3.00
	COMPOSITE MARKUPS FOR S			
	MATERIAL COMPOSITE MARKUP	1.201		
	LABOR COMPOSITE MARKUP	1.201		
	EQUIPMENT COMPOSITE MARKUP	1.201		

PROJECT: Red Hill Tank 19 - Repair Existing
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

DETAIL REPORT
 UNBURDENED LINE ITEMS
 FACD
 SOFTWARE VERSION: SUCCESS 3.0
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT PRL 98-9

DATABASE USED: EEI
 PRINTING DATE: 05/27/1998

PROJECT: Red Hill Tank 19 - Repair Existing
 CONSTRUCTION CONTRACT: PRL 98-9

PRINTING DATE: 05/27/1998
 Page No. 1

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
00							
0001							
	0001 FIELD OVERHEAD						
	<i>This system is distributed</i>						
010000002	Project Superintendent	12.00	mos	0	5940	0	5940
					71,280		71,280
010000002	Project Quality Control	12.00	mos	0	5000	0	5000
					60,000		60,000
010000002	Safety	10.00	mos	0	4800	0	4800
					48,000		48,000
010000002	Firewatch	10.00	mos	0	4800	0	4800
					48,000		48,000
010000002	Equipment Operator (fork truck)	7.00	mos	0	4800	0	4800
					33,600		33,600
010000002	Boom Operator	10.00	mos	0	5300	0	5300
					53,000		53,000
010000001	Pick-Up Truck #1	10.00	mos	0	0	720	720
						7,200	7,200
010000001	Pick-Up Truck #2	10.00	mos	0	0	720	720
						7,200	7,200
010000001	Skid Steer/fork lift #1	10.00	mos	0	0	2530	2530
						25,300	25,300
010000001	Fork Lift #2	6.00	mos	0	0	2530	2530
						15,180	15,180
010000001	Welding Equipment #1	6.00	mos	0	0	600	600
						3,600	3,600
010000001	Welding Equipment #2	6.00	mos	0	0	600	600
						3,600	3,600
010000003	Contractor Office	10.00	mos	0	0	181	181
						1,810	1,810
010000003	Tool & Storage Shed	10.00	mos	0	0	90	90
						900	900
010000003	Temporary Toilets	10.00	mos	0	0	80	80
						800	800
010000003	Small Tools	10.00	mos	0	0	750	750
						7,500	7,500
010000003	Construction Schedule	1.00	LS	0	1200	0	1200
					1,200		1,200

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
0001 FIELD OVERHEAD							
<i>This system is distributed</i>							
010000003	Progress Sched	10.00	mos	0	240	0	240
				0	2,400	0	2,400
010000004	Photographs	10.00	mos	50	0	0	50
				500	0	0	500
010000004	Submittals	3.00	wk	0	1500	0	1500
				0	4,500	0	4,500
010000004	As-Built Drawings	3.00	wk	400	1500	0	1900
				1,200	4,500	0	5,700
010000006	Communications: Telephone, Radios	10.00	mos	0	0	247	247
				0	0	2,470	2,470
010000014	General Clean-up	10.00	mos	0	300	0	300
				0	3,000	0	3,000
010000014	Mobilization	1.00	LS	3000	7000	0	10000
				3,000	7,000	0	10,000
010000014	Demobilization	1.00	LS	0	7000	0	7000
				0	7,000	0	7,000
TOTAL 0001 FIELD OVERHEAD				4,700	343,480	75,560	423,740
1.00 LS							

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
10							
1010							
101010							
101010001 General							
Subcontractor: S		1.00	ls	6000	9600	4500	20100
Temp. monorail in tank (s12 x 35 monorail + 2 hoists)				6,000	9,600	4,500	20,100
		20.00	mos			1025	1025
Temp. swing staging inside tank (rented air powered, to 300' high, 2 stages)				0	0	20,500	20,500
Subcontractor: S		2.00	ea		500		500
Certify Booms				0	1,000	0	1,000
Subcontractor: S		2.00	ea		500		500
Certify Swing Staging				0	1,000	0	1,000
Subcontractor: S		1.00	ls	13800	7393		21193
Temp power to Const Trailers				13,800	7,393	0	21,193
Subcontractor: S		1.00	ls	10357	6071		16428
Elec - Upper Tunnel - Weld, elec, lights, small tools				10,357	6,071	0	16,428
Subcontractor: S		1.00	ls	14964	4321		19285
Elec - Lower Tunnel - Weld, elec, lights, small tools				14,964	4,321	0	19,285
		2.00	md		240	50	290
Remove Exist. Aboveground Air Supply Fan at top of tank				0	480	100	580
		2.00	md		240	50	290
Remove ductwork, Lower Tunnel				0	480	100	580
		40.00	md		240		240
Remove Hoist Sys. / swing staging (4per. @ 30/hr x 8hr/day x 10 day)				0	9,600	0	9,600
		8.00	md		240		240
Remove Lighting in Tank (2per. @ 30/hr x 8hr/day x 4 day)				0	1,920	0	1,920
		20.00	md		240		240
Water Wash Shell & Tower (4per. @ 30/hr x 8hr/day x 5 day)				0	4,800	0	4,800
Subcontractor: S		10.00	day		750		750
Marine Chemist - Evaluation				0	7,500	0	7,500
Subcontractor: S		3.00	day		750		750
Marine Chemist - Safety Pan				0	2,250	0	2,250
Subtotal Direct Costs				45,121	56,415	25,200	126,736
Subcontractor Markups				9,068	7,865	904	17,838
Distributions				281	32,224	4,267	36,772
Prime Contractor P Markups				19,627	151,615	10,738	181,980
TOTAL 101010001 General				74,098	248,119	41,110	363,326
1.00 LS							

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
101010							
	101010001 General						
	SUBTOTAL 101010 General			45,121	56,415	25,200	126,736
	MARKUP			1,642	4,398	1,631	2,867
	TOTAL 101010 General			74,098	248,119	41,110	363,326
101011							
	101011001 Ventilation System						
	Subcontractor: S	1.00	ea	14000	1000		15000
	Supply fan with filters, 19000 l/s, 100 hp motor (75 kw motor)			14,000	1,000	0	15,000
	Subcontractor: S	1.00	ea	16000	1500		17500
	Exhaust fan with filters, 19000 l/s, 100 hp motor (75 kw motor)			16,000	1,500	0	17,500
	Subcontractor: S	50.00	m	43	62		105
	Ductwork, 800 mm dia			2,150	3,100	0	5,250
	Subcontractor: S	200.00	m	13	16		29
	Flex duct, 300 mm dia			2,600	3,200	0	5,800
	Subcontractor: S	1.00	ea		1004	44118	45122
	Elec - Gen for Supply Fan			0	1,004	44,118	45,122
	Subcontractor: S	1.00	ea		11250		11250
	Elec - Gen Demob			0	11,250	0	11,250
	Subtotal Direct Costs			34,750	21,054	44,118	99,922
	Subcontractor Markups			6,984	4,231	8,867	20,082
	Distributions			217	12,676	8,661	21,554
	Prime Contractor P Markups			15,116	59,639	21,795	96,550
	TOTAL 101011001 Ventilation System			57,067	97,600	83,441	238,108
	1.00 LS						
	101011002 Baghouse Dust Collection						
	Subcontractor: S	1.00	ea	15000	1100	0.1	16100.1
	Dust collector (bag house) with filters & cleaning system			15,000	1,100	0	16,100
	Subcontractor: S	1.00	ea	9000	950		9950
	Exhaust Fan, in line centrifugal 9500 L/s, 20 hp			9,000	950	0	9,950
	Subcontractor: S	15.00	m	50	70		120
	Ductwork 900 mm dia			750	1,050	0	1,800
	Subtotal Direct Costs			24,750	3,100	0	27,850
	Subcontractor Markups			4,974	623	0	5,597
	Distributions			154	1,866	0	2,021
	Prime Contractor P Markups			10,766	8,781	0	19,547
	TOTAL 101011002 Baghouse Dust Collection			40,645	14,371	0	55,015
	1.00 LS						
	SUBTOTAL 101011 Ventilation			59,500	24,154	44,118	127,772
	MARKUP			1,642	4,636	1,891	2,294
	TOTAL 101011 Ventilation			97,711	111,971	83,442	293,124

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
101012							
	<u>101012001 Dehumidification</u>						
	Subcontractor: S	2.00	ea	7000	1500	1	8501
	Dehumid. - Air Handling Unit, 4750 L/S, 10 HP motor, w/reheat			14,000	3,000	2	17,002
	Subcontractor: S	2.00	ea	50000	6600		56600
	Dehumid. - Air Cooled condensing unit, 270 KW capacity			100,000	13,200	0	113,200
	Subcontractor: S	1.00	ea	1000	1000		2000
	Dehumid. - Refrigerant piping & accessories			1,000	1,000	0	2,000
	Subtotal Direct Costs			115,000	17,200	2	132,202
	Subcontractor Markups			23,113	3,457	0	26,570
	Distributions			717	10,355	0	11,073
	Prime Contractor P Markups			50,023	48,722	1	98,747
	TOTAL 101012001 Dehumidification			188,853	79,734	4	268,591
	1.00 LF						
	 SUBTOTAL 101012 Dehumidification			115,000	17,200	2	132,202
	MARKUP			1.642	4.636	1.890	2.032
	TOTAL 101012 Dehumidification			188,853	79,734	4	268,591
	 SUBTOTAL 1010 MAINTENANCE			219,621	97,769	69,320	386,710
	MARKUP			1.642	4.499	1.797	2.392
	TOTAL 1010 MAINTENANCE			360,662	439,824	124,555	925,041
1011							
	101110						
	<u>101110001 Demo Piping & Tell-tale In Tank</u>						
	Remove Tell-tale piping, DN 20	357.00	m		8		8
				0	2,856	0	2,856
	Remove Tell-tale piping, DN 40	615.00	m		10		10
				0	6,150	0	6,150
	Remove Tell-tale jumper pipes, DN20	163.00	ea		10		10
				0	1,630	0	1,630
	Remove gooseneck DN 800, Fill/Issue	16.00	mh		25		25
				0	400	0	400
	Remove tee, reducer & valve, DN 400	12.00	mh		25		25
				0	300	0	300
	Remove water piping in tank	8.00	mh		25		25
				0	200	0	200
	Remove water piping in tunnel	12.00	mh	0.1	25	0.1	25.2
				1	300	1	302
	Material Disposal	8000.00	kg		0.3		0.3
				0	2,400	0	2,400

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
101110							
101110001 Demo Piping & Tell-tale In Tank							
	Subtotal Direct Costs			1	14,236	1	14,238
	Distributions			0	7,136	0	7,137
	Prime Contractor P Markups			0	33,578	0	33,579
	TOTAL 101110001 Demo Piping & Tell-tale In Tank			2	54,950	2	54,954
	1.00 LS						
	SUBTOTAL 101110 Demo Piping & Tell-tale In Tank			1	14,236	1	14,238
	MARKUP			1.367	3.860	1.575	3.860
	TOTAL 101110 Demo Piping & Tell-tale In Tank			2	54,950	2	54,954
	SUBTOTAL 1011 REPAIR			1	14,236	1	14,238
	MARKUP			1.367	3.860	1.575	3.860
	TOTAL 1011 REPAIR			2	54,950	2	54,954

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
11							
1110							
111010							
111010001 Basic Tank Repairs & Appurtanences							
Remove Grout Tubes	500.00	ea		0	15 7,500	0	15 7,500
Remove All Misc Clips / Debris	1.00	ls		0	1000 1,000	0	1000 1,000
Patch Plate Holes at Removed Tell tale Piping / Grout Tubes	1000.00	ea		10 10,000	60 60,000	0	70 70,000
Subtotal Direct Costs				10,000	68,500	0	78,500
Distributions				52	34,339	0	34,391
Prime Contractor P Markups				3,622	161,567	0	165,189
TOTAL 111010001 Basic Tank Repairs & Appurtanences				13,674	264,406	0	278,080
1.00 LF							
SUBTOTAL 111010 Basic Tank Repairs & Appurtanences				10,000	68,500	0	78,500
MARKUP				1.367	3.860		3.542
TOTAL 111010 Basic Tank Repairs & Appurtanences				13,674	264,406	0	278,080
SUBTOTAL 1110 MAINTENANCE				10,000	68,500	0	78,500
MARKUP				1.367	3.860		3.542
TOTAL 1110 MAINTENANCE				13,674	264,406	0	278,080
1111							
111110							
111110001 Basic Tank Repairs & Appurtanences							
Subcontractor: S Tank Piping - DN 800 diffuser	4.00	m		2300 9,200	1050 4,200	440 1,760	3790 15,160
Subcontractor: S Tank Piping - DN 400 piping mods.	2.00	m		583 1,166	262 524	110 220	955 1,910
Subcontractor: S Tank Piping - DN 200 piping mods.	2.00	m		146 292	66 132	28 56	240 480
Subcontractor: S Tank Piping - Hydrotest	1.00	ls		2000 2,000	2400 2,400	0	4400 4,400
Subcontractor: S Tank strapping & calibration	1.00	ls		0	12000 12,000	1000 1,000	13000 13,000
Tower Mods. - Reinf @ Dome for Boom Operation, 4 per @ 30/hr x 8hr/day x 7 days) ^a	7.00	md		1000 7,000	240 1,680	0	1240 8,680
Tower Mods. - Provide Gauging Platform	10.00	md		1000 10,000	240 2,400	0	1240 12,400
Tank ATG - Remove existing gauge system	2.00	md		0	240 480	0	240 480
ATG system (type to be determined)	1.00	ea		25000 25,000	1500 1,500	0	26500 26,500

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
111110							
	111110001 Basic Tank Repairs & Appurtanences						
	Subcontractor: S	1.00	ea		1000		1000
	Tank ATG - System testing			0	1,000	0	1,000
	Subcontractor: S	1.00	ea	1732	5000		6732
	Elec wire and conduits for ATG system			1,732	5,000	0	6,732
	Subtotal Direct Costs			56,390	31,316	3,036	90,742
	Subcontractor Markups			2,892	5,076	610	8,578
	Distributions			308	18,243	596	19,147
	Prime Contractor P Markups			21,472	85,836	1,500	108,807
	TOTAL 111110001 Basic Tank Repairs & Appurtanences			81,061	140,471	5,742	227,274
	1.00 LF						
	SUBTOTAL 111110 Basic Tank Repairs & Appurtanences			56,390	31,316	3,036	90,742
	MARKUP			1,438	4,486	1,891	2,505
	TOTAL 111110 Basic Tank Repairs & Appurtanences			81,061	140,471	5,742	227,274
	SUBTOTAL 1111 REPAIR			56,390	31,316	3,036	90,742
	MARKUP			1,438	4,486	1,891	2,505
	TOTAL 1111 REPAIR			81,061	140,471	5,742	227,274
1112							
	111210						
	111210001 Basic Tank Repairs & Appurtanences						
	Subcontractor: S	1.00	ea	3500	1000		4500
	Hi level control panel, Scully system			3,500	1,000	0	4,500
	Subcontractor: S	2.00	ea	250	80		330
	Hi level alarm sensors			500	160	0	660
	Subcontractor: S	1.00	ea	150	480		630
	Hi level alarm sensor holder, tank mods			150	480	0	630
	Subcontractor: S	1.00	ea	1732	5000		6732
	Elec wire and conduits for hi level alarm system			1,732	5,000	0	6,732
	Subtotal Direct Costs			5,882	6,640	0	12,522
	Subcontractor Markups			1,182	1,335	0	2,517
	Distributions			37	3,998	0	4,034
	Prime Contractor P Markups			2,559	18,809	0	21,368
	TOTAL 111210001 Basic Tank Repairs & Appurtanences			9,659	30,781	0	40,441
	1.00 LF						
	SUBTOTAL 111210 Basic Tank Repairs & Appurtanences			5,882	6,640	0	12,522
	MARKUP			1,642	4,636		3,230
	TOTAL 111210 Basic Tank Repairs & Appurtanences			9,659	30,781	0	40,441
	SUBTOTAL 1112 MINOR CONSTRUCTION			5,882	6,640	0	12,522
	MARKUP			1,642	4,636		3,230
	TOTAL 1112 MINOR CONSTRUCTION			9,659	30,781	0	40,441

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
111210	<u>111210001 Basic Tank Repairs & Appurtanences</u>						

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
12							
1210							
121010							
	<u>121010001 Repair Exist.Tank - Lower Dome</u>						
	Remove existing NRL Coating: Lower Dome (quote)	1460.00	m2	21.53 31,434	25.64 37,434	0	47.17 68,868
	Patch Plate Repair holes/thin spots	400.00	ea	10 4,000	60 24,000	0	70 28,000
	Repair existing welds (150 long)	400.00	ea	10 4,000	60 24,000	0	70 28,000
	Sawcut 3' x 3' a 12" for sump/remove concrete	0.25	m2	0	325 81	0	325 81
	600 DN sump, grout and weld in place	1.00	ea	350 350	480 480	0	830 830
	Subtotal Direct Costs			39,784	85,996	0	125,779
	Distributions			207	43,109	0	43,316
	Prime Contractor P Markups			14,409	202,834	0	217,243
	TOTAL 121010001 Repair Exist.Tank - Lower Dome			54,400	331,939	0	386,338
	1.00 LF						
	SUBTOTAL 121010 Repair Exist Tank - Lower Dome			39,784	85,996	0	125,779
	MARKUP			1.367	3.860		3.072
	TOTAL 121010 Repair Exist.Tank - Lower Dome			54,400	331,939	0	386,338
	SUBTOTAL 1210 MAINTENANCE			39,784	85,996	0	125,779
	MARKUP			1.367	3.860		3.072
	TOTAL 1210 MAINTENANCE			54,400	331,939	0	386,338

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
13							
1310							
131010							
	<u>131010001 Repair Exist.Tank - Barrel</u>						
	Remove existing NRL Coating: Barrel (quote)	4400.00	m2	21.53 94,732	25.64 112,816	0	47.17 207,548
	Patch Plate Repair holes/thin spots	600.00	ea	10 6,000	60 36,000	0	70 42,000
	Repair existing welds (150 long)	600.00	ea	10 6,000	60 36,000	0	70 42,000
	Subtotal Direct Costs			106,732	184,816	0	291,548
	Distributions			554	92,648	0	93,202
	Prime Contractor P Markups			38,657	435,916	0	474,573
	TOTAL 131010001 Repair Exist.Tank - Barrel			145,944	713,380	0	859,323
	1.00 LF						
	 SUBTOTAL 131010 Repair Exist.Tank - Barrel			106,732	184,816	0	291,548
	MARKUP			1.367	3.860		2.947
	TOTAL 131010 Repair Exist.Tank - Barrel			145,944	713,380	0	859,323
	 SUBTOTAL 1310 MAINTENANCE			106,732	184,816	0	291,548
	MARKUP			1.367	3.860		2.947
	TOTAL 1310 MAINTENANCE			145,944	713,380	0	859,323

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
14							
1411							
141110							
	<u>141110001 Repair Exist. Tell-tale Sys.- Ppg. to Sump</u>						
		300.00	m	17	27	3	47
Pipe, DN 40, Sched 80, including fittings				5,100	8,100	900	14,100
		26.00	m	21	34	4	59
Pipe, DN 50, Sched 80, including fittings				546	884	104	1,534
		17.00	m	107	102	7	216
Pipe, DN 150, Sched 80, including fittings				1,819	1,734	119	3,672
		10.00	m	660	450	31	1,141
Pipe, DN 450, Sched 40, including fittings				6,600	4,500	310	11,410
		13.00	ea	150	55	6	211
Valve, DN 40, Gate				1,950	715	78	2,743
		1.00	ea	190	70	8	268
Valve, DN 50, Gate				190	70	8	268
Subcontractor: S		20.00	md		240		240
NDE welds				0	4,800	0	4,800
Subcontractor: S		8.00	md		240		240
Hydrotest telltale				0	1,920	0	1,920
Subtotal Direct Costs				16,205	22,723	1,519	40,447
Subcontractor Markups				0	1,351	0	1,351
Distributions				84	12,068	248	12,400
Prime Contractor P Markups				5,869	56,781	625	63,275
TOTAL 141110001 Repair Exist. Tell-tale Sys.- Ppg. to Sump				22,158	92,923	2,392	117,473
	1.00 LS						
	<u>141110002 New Tell-tale System - Piping to Sump - Structural</u>						
		1.00	ls	500	400		900
Grout				500	400	0	900
Subcontractor: S		17.00	m	125	250	40	415
Drill concrete, 254 mm dia.				2,125	4,250	680	7,055
Subcontractor: S		10.00	m	570	1600	260	2430
Drill concrete, 610 mm dia				5,700	16,000	2,600	24,300
Subtotal Direct Costs				8,325	20,650	3,280	32,255
Subcontractor Markups				1,573	4,070	659	6,302
Distributions				51	12,392	644	13,087
Prime Contractor P Markups				3,585	58,305	1,620	63,511
TOTAL 141110002 New Tell-tale System - Piping to Sump - Structural				13,534	95,417	6,204	115,155
	1.00 LS						
SUBTOTAL 141110 Repair Exist. Tell-tale Sys.				24,530	43,373	4,799	72,702
MARKUP				1,455	4,342	1,791	3,200
TOTAL 141110 Repair Exist. Tell-tale Sys.				35,692	188,340	8,596	232,628

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
141110	<u>141110002 New Tell-tale System - Piping to Sump - Structural</u>						
SUBTOTAL 1411 REPAIR				24,530	43,373	4,799	72,702
MARKUP				1,455	4,342	1,791	3,200
TOTAL 1411 REPAIR				35,692	188,340	8,596	232,628

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
15							
1510							
151010							
	<u>151010001 Upper Dome Repairs</u>						
	Subcontractor: S	5.00	days			2821	2821
	UTscan 10% Dome			0	0	14,105	14,105
		250.00	ea	10	60		70
	Patch plate thin spots/holes			2,500	15,000	0	17,500
	Subcontractor: S	75.00	m2	51.45	43		94.45
	Spot coating repair			3,859	3,225	0	7,084
	Subtotal Direct Costs			6,359	18,225	14,105	38,689
	Subcontractor Markups			776	648	2,835	4,259
	Distributions			37	9,461	2,769	12,267
	Prime Contractor P Markups			2,584	44,515	6,968	54,067
	TOTAL 151010001 Upper Dome Repairs			9,755	72,849	26,677	109,282
	1.00 LF						
	 SUBTOTAL 151010 Upper Dome Repairs			6,359	18,225	14,105	38,689
	MARKUP			1,534	3,997	1,891	2,825
	TOTAL 151010 Upper Dome Repairs			9,755	72,849	26,677	109,282
	 SUBTOTAL 1510 MAINTENANCE			6,359	18,225	14,105	38,689
	MARKUP			1,534	3,997	1,891	2,825
	TOTAL 1510 MAINTENANCE			9,755	72,849	26,677	109,282

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
16							
1610							
161010							
	<u>161010001 Existing Tank Investigation</u>						
	100% UT scan Barrel & Lower Dome (quote)	1.00	ls	0	0	98500	98500
						98,500	98,500
	Helium Leak test	56.00	md	0	240	0	240
					13,440	0	13,440
	Helium leak test equipment	28.00	day	0	0	100	100
						2,800	2,800
	Helium cylinders	150.00	ea	50	0	0	50
				7,500	0	0	7,500
	Drill and tap helium test holes	5.00	md	0	240	0	240
					1,200	0	1,200
	Patch Helium test holes	1000.00	ea	10	60	0	70
				10,000	60,000	0	70,000
	Subtotal Direct Costs			17,500	74,640	101,300	193,440
	Distributions			91	37,417	16,559	54,067
	Prime Contractor P Markups			6,338	176,050	41,670	224,057
	TOTAL 161010001 Existing Tank Investigation			23,929	288,106	159,529	471,565
	1.00 LF						
	 SUBTOTAL 161010 Existing Tank Investigation			17,500	74,640	101,300	193,440
	MARKUP			1.367	3.860	1.575	2.438
	TOTAL 161010 Existing Tank Investigation			23,929	288,106	159,529	471,565
	 SUBTOTAL 1610 MAINTENANCE			17,500	74,640	101,300	193,440
	MARKUP			1.367	3.860	1.575	2.438
	TOTAL 1610 MAINTENANCE			23,929	288,106	159,529	471,565

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
17							
1710							
171010							
	<u>171010001 Recoat Exist.Tank - Lower Dome</u>						
	FNEC Coating: Lower Dome (quote)	1460.00	m2	31.57 46,092	0	15.07 22,002	46.64 68,094
	Prep lower dome for coating (quote)	1460.00	m2	21.23 30,996	0	23.27 33,974	44.5 64,970
	Subtotal Direct Costs			77,088	0	55,976	133,064
	Distributions			400	0	9,150	9,551
	Prime Contractor P Markups			27,921	0	23,026	50,946
	TOTAL 171010001 Recoat Exist.Tank - Lower Dome			105,409	0	88,153	193,562
	1.00 LF						
	 SUBTOTAL 171010 Recoat Exist.Tank - Lower Dome			77,088	0	55,976	133,064
	MARKUP			1.367		1.575	1.455
	TOTAL 171010 Recoat Exist.Tank - Lower Dome			105,409	0	88,153	193,562
	 SUBTOTAL 1710 MAINTENANCE			77,088	0	55,976	133,064
	MARKUP			1.367		1.575	1.455
	TOTAL 1710 MAINTENANCE			105,409	0	88,153	193,562

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
18							
1810							
181010							
	<u>181010001 Recoat Exist.Tank - Barrel</u>						
		4400.00	m2	30.45 133,980	0	17.03 74,932	47.48 208,912
	FNEC Coating: Barrel (flexiblized Novalac epoxy) (quote)						
		4400.00	m2	21 92,400	0	25.7 113,080	46.7 205,480
	Prep Barrel for coating (quote)						
	Subtotal Direct Costs			226,380	0	188,012	414,392
	Distributions			1,176	0	30,734	31,910
	Prime Contractor P Markups			81,993	0	77,338	159,331
	TOTAL 181010001 Recoat Exist.Tank - Barrel			309,549	0	296,085	605,633
	1.00 LF						
	 SUBTOTAL 181010 Recoat Exist.Tank - Barrel			226,380	0	188,012	414,392
	MARKUP			1.367		1.575	1.461
	TOTAL 181010 Recoat Exist.Tank - Barrel			309,549	0	296,085	605,633
	 SUBTOTAL 1810 MAINTENANCE			226,380	0	188,012	414,392
	MARKUP			1.367		1.575	1.461
	TOTAL 1810 MAINTENANCE			309,549	0	296,085	605,633

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
19							
1910							
191010							
	<u>191010001 Tank Piping - Lining</u>						
	Subcontractor: S	17.00	m	2300	1050	440	3790
	Tank Piping - Fuel, Pipe Lining - DN 800			39,100	17,850	7,480	64,430
	Subcontractor: S	17.00	m	583	262	110	955
	Tank Piping - Fuel, Pipe Lining - DN 400			9,911	4,454	1,870	16,235
	Subcontractor: S	17.00	m	146	66	28	240
	Tank Piping - Fuel, Pipe Lining - DN 200			2,482	1,122	476	4,080
	Subcontractor: S	1.00	ls	2000	2400		4400
	Tank Piping - Hydrotest			2,000	2,400	0	4,400
	Subtotal Direct Costs			53,493	25,826	9,826	89,145
	Subcontractor Markups			10,751	5,191	1,975	17,916
	Distributions			334	15,548	1,929	17,811
	Prime Contractor P Markups			23,269	73,157	4,854	101,280
	TOTAL 191010001 Tank Piping - Lining			87,846	119,722	18,584	226,153
	1.00 LF						
	 SUBTOTAL 191010 Tank Piping - Lining			53,493	25,826	9,826	89,145
	MARKUP			1.642	4.636	1.891	2.537
	TOTAL 191010 Tank Piping - Lining			87,846	119,722	18,584	226,153
	 SUBTOTAL 1910 MAINTENANCE			53,493	25,826	9,826	89,145
	MARKUP			1.642	4.636	1.891	2.537
	TOTAL 1910 MAINTENANCE			87,846	119,722	18,584	226,153

**REPAIR AND RECOAT EXISTING TANK
COST ESTIMATE - ADDITIVE BID ITEMS**

SYSTEM REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-repe

PROJECT: Red Hill Tank 19 - Rep. Exis, Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON 1 PRL 98 UNITS/ U/M	SYSTEM	COST/WBS UNIT	TOTAL MARKED UP COSTS			
					MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)								747,000
*****PROJECT SUBTOTALS****					97,880	560,490	88,985	747,356
	<u>ADDITIVE BID ITEMS</u>	747355.80/PRL	1 LS		97,880	560,490	88,985	747,356
<u>35</u>	<u>-Cathodic Protection</u>	<u>550955.13/PRL</u>	<u>1 LS</u>		<u>77,020</u>	<u>473,925</u>	<u>11</u>	<u>550,955</u>
	MAINTENANCE	550955.13/PRL	1 LS		77,020	473,925	11	550,955
<u>40</u>	<u>-Under Tank Leak Detection</u>	<u>85311.61/PRL</u>	<u>1 LS</u>		<u>0</u>	<u>0</u>	<u>85,312</u>	<u>85,312</u>
	MINOR CONSTRUCTION	85311.61/PRL	1 LS		0	0	85,312	85,312
<u>45</u>	<u>-New Tell-tale System - Piping T</u>	<u>111089.06/PRL</u>	<u>1 LS</u>		<u>20,861</u>	<u>86,565</u>	<u>3,663</u>	<u>111,089</u>
	REPAIR	111089.06/PRL	1 LS		20,861	86,565	3,663	111,089

SUMMARY REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.21
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED: EEI
 PRINTING DATE: 05/27/1998
 Page No. 1
 ESTIMATE NAME: T19-repe

PROJECT: Red Hill Tank 19 - Rep. Exis, Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 CONSTRUCTION FUNDS AVAILABLE:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

WBS CODE	DESCRIPTION	COST/WBS BASED ON	SYSTEM	COST/WBS	TOTAL MARKED UP COSTS			
		1 PRL 98	UNITS/ U/M	UNIT	MATL	LABOR	EQUIP	TOTAL
TOTAL ESTIMATED CONTRACT (ROUNDED)								747,000
*****PROJECT SUBTOTALS****					97,880	560,490	88,985	747,356
	<u>ADDITIVE BID ITEMS</u>	<u>747355.80/PRL</u>	<u>1 LS</u>		<u>97,880</u>	<u>560,490</u>	<u>88,985</u>	<u>747,356</u>
35	---Cathodic Protection	550955.13/PRL	1 LS		77,020	473,925	11	550,955
40	---Under Tank Leak Detection	85311.61/PRL	1 LS		0	0	85,312	85,312
45	---New Tell-tale System - Pipi	111089.06/PRL	1 LS		20,861	86,565	3,663	111,089

CONTRACTOR MARKUP REPORT
 SUBMITTAL: FACD
 SOFTWARE VERSION: SUCCESS 2.1
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT: PRL 98-9
 DATABASE USED :EEI
 PRINTING DATE :05/27/98
 PAGE NUMBER :1
 ESTIMATE NAME : T19-repexis,

PROJECT: Red Hill Tank 19 - Rep. Exis, Additive Bid Items
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR:EEI
 PROJECT SIZE: 1.00PRL 98-9
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE:N/A
 UIC:
 PROJECT #:
 DATE OF ESTIMATE:5/26/98
 BID DATE: 4/99

CONTRACTOR	DESCRIPTION	MATERIAL	LABOR	EQUIPMENT
P	Prime Contractor			
	WORKER'S COMPENSATION/UNEMPL/SOC. SEC TAXES	0.00	32.00	0.00
	Hawaii cost adjustment compared to AK	0.00	31.00	0.00
	PRIME OVERHEAD	10.00	10.00	10.00
	PRIME PROFIT	6.00	6.00	6.00
	PRIME HOME OFFICE	3.00	3.00	3.00
	BOND	1.00	1.00	1.00
	ESCALATION	1.02	1.02	1.02
	ESTIMATING CONTINGENCY	5.00	5.00	5.00
	HI GET	4.17	4.17	4.17
	SALES TAX	0.50	0.00	0.50
	COMPOSITE MARKUPS FOR P			
	MATERIAL COMPOSITE MARKUP	1.347		
	LABOR COMPOSITE MARKUP	2.318		
	EQUIPMENT COMPOSITE MARKUP	1.347		
S	Subcontractors			
	SUBCONTRACTOR OVERHEAD	10.00	10.00	10.00
	SUBCONTRACTOR PROFIT	6.00	6.00	6.00
	SUBCONTRACTOR HOME OFFICE	3.00	3.00	3.00
	COMPOSITE MARKUPS FOR S			
	MATERIAL COMPOSITE MARKUP	1.201		
	LABOR COMPOSITE MARKUP	1.201		
	EQUIPMENT COMPOSITE MARKUP	1.201		

PROJECT: Red Hill Tank 19 - Rep. Exis, Additive B
 LOCATION: FISC Pearl Harbor, HI
 ESTIMATOR: EEI
 PROJECT SIZE: 1 PRL 98
 AUTHORIZED CONSTRUCTION FUNDS:

CAT CODE: N/A
 UIC:
 PROJECT #: PRL 98-9
 DATE OF ESTIMATE: 5/26/98
 BID DATE: 4/99

DETAIL REPORT
 UNBURDENED LINE ITEMS
 FACD
 SOFTWARE VERSION: SUCCESS 3.0
 REPORT WRITER VERSION: R&R 6.0

CONSTRUCTION CONTRACT PRL 98-9

DATABASE USED: EEI
 PRINTING DATE: 05/27/1998

PROJECT: Red Hill Tank 19 - Rep. Exis, Additive B
 CONSTRUCTION CONTRACT: PRL 98-9

PRINTING DATE: 05/27/1998
 Page No. 1

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
35							
3500							
350010							
	<u>3500100 Cathodic Protection</u>						
	Anodes (MMO 19.1 mm x 1219 mm)	48.00	ea	150 7,200	8 384	0	158 7,584
	Anode Ventralizer Assembly	48.00	ea	28 1,344	8 384	0	36 1,728
	Anode Lead Wire, No 4 AWG, HMWPE	869.00	m	1.27 1,104	0	0	1.27 1,104
	Subcontractor: S Anode Hole Drilling & Backfilling Complete	580.00	m	0	255 147,900	0	255 147,900
	Subcontractor: S Coke Backfill	13581.00	kg	1.5 20,372	0	0	1.5 20,372
	Subcontractor: S Cement Grout	6.67	m3	140 934	0	1 7	141 940
	Anode Vent Pipe	580.00	m	3.56 2,065	0	0	3.56 2,065
	Custom Anode Junction Box (NEMA 4X)	4.00	ea	280 1,120	295 1,180	0	575 2,300
	Oil-Cooled Rectifier, 50 Volt, 200 DC Amp	1.00	ea	3100 3,100	1500 1,500	0	4600 4,600
	Rectifier Oil	322.00	liters	1.58 509	7 2,254	0	8.58 2,763
	Subcontractor: S 240 Volt, 20 Amp AC power for rectifier	1.00	ea	760 760	1100 1,100	0	1860 1,860
	Subcontractor: S AC Disconnect Switch, Fused 3P-40 Amp	1.00	ea	220 220	120 120	0	340 340
	Rectifier Pipe Bollards complete	3.00	ea	32 96	110 330	0	142 426
	Subcontractor: S Micro Directional Drill for 5 Ref Electrodes	60.00	m	0	32 1,920	0	32 1,920
	Reference Electrodes (2 per hole)	10.00	ea	245 2,450	0	0	245 2,450
	Concrete Electrical Pull Box	4.00	ea	190 760	32 128	0	222 888
	Concrete Pads (inc rebar & forms)	0.72	m3	155 112	616 444	0	771 555

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
350010							
<u>3500100 Cathodic Protection</u>							
		50.00	m	5.04 252	7 350	0	12.04 602
	Cathode Header Cable, # 2/0 AWG HMP/PE						
		320.00	m	5.04 1,613	2.12 678	0	7.16 2,291
	Anode Header Cable, #2/0 AWG HMP/PE						
		320.00	m	5 1,600	2.12 678	0	7.12 2,278
	50 mm PVC conduit (anode cables)						
	Subcontractor: S	150.00	m		5.5		5.5
	Trenching (Min. 0.1 m wide x 0.68 m deep)			0	825	0	825
	Subcontractor: S	150.00	m		5.5		5.5
	Trench Backfilling & Compaction			0	825	0	825
	Subcontractor: S	2.40	m3	120			120
	Bedding Sand (Min. 0.1 m wide x 0.16 m deep)			288	0	0	288
		256.00	hrs		20		20
	Cathodic Protection construction foreman			0	5,120	0	5,120
		256.00	hrs	26.35 6,746	30 7,680	0	56.35 14,426
	QC Specialist, Corrosion Engineer						
Subtotal Direct Costs				52,642	173,800	7	226,449
Subcontractor Markups				4,537	30,688	1	35,226
Prime Contractor P Markups				19,840	269,437	3	289,280
TOTAL 3500100 Cathodic Protection				77,020	473,925	11	550,955
1.00 LS							
SUBTOTAL 35001 Cathodic Protection				52,642	173,800	7	226,449
MARKUP				1.463	2.727	1.610	2.433
TOTAL 35001 Cathodic Protection				77,020	473,925	11	550,955

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
40							
4000							
400010							
	<u>4000100 Under Tank Leak Detection</u>						
	Subcontractor: S	10.00	day			3500	3500
	Drill Rig (10) 38 to 50 DN Directional			0	0	35,000	35,000
	Boring x 46 long ea						
	Subcontractor: S	1.00	ls			18000	18000
	Mob/Demob			0	0	18,000	18,000
	Subtotal Direct Costs			0	0	53,000	53,000
	Subcontractor Markups			0	0	10,652	10,652
	Prime Contractor P Markups			0	0	21,660	21,660
	TOTAL 4000100 Under Tank Leak Detection			0	0	85,312	85,312
	1.00 LS						
	SUBTOTAL 40001 Under Tank Leak Detection			0	0	53,000	53,000
	MARKUP					1,610	1,610
	TOTAL 40001 Under Tank Leak Detection			0	0	85,312	85,312

WBS CODE	DESCRIPTION	QTY	UM	MATERIAL	LABOR	EQUIPMENT	TOTAL
45							
4501							
	<u>4501 New Tell-tale System - Piping to top of tank</u>						
	Pipe, DN 40, Sched 80	911.00	m	17 15,487	41 37,351	3 2,733	61 55,571
	Subtotal Direct Costs			15,487	37,351	2,733	55,571
	Prime Contractor P Markups			5,374	49,214	930	55,518
	TOTAL 4501 New Tell-tale System - Piping to top of tank			20,861	86,565	3,663	111,089
	1.00 LS						

SUBTOTAL 45 New Tell-tale System - Piping To Top Of Tank	15,487	37,351	2,733	55,571
MARKUP	1,347	2,318	1,340	1,999
TOTAL 45 New Tell-tale System - Piping To Top Of T	20,861	86,565	3,663	111,089